

Preliminaries for the installation of access and hollow floor*

1. Constructional and assembly drawing

Site measurement starts acc. to the binding constructional drawings of the buyer. The assembly drawing which is worked out thereupon has to be confirmed by the buyer and is decisive for the installation.

2. Terms of delivery and Installation

have to be agreed in written. Postponements to a later date have to be indicated at least two weeks before the first agreed date. Earlier installation dates than agreed must always be checked and coordinated with our assembly department.

3. Unloading, transport and storing

Unless otherwise agreed unloading and transport of material to the installation room is done by MERO-TSK. If floating floor screed is required silo truck and mixer must have free access to the jobsite. Space for screed pump and screed mixer must be available.

If transport and storing of material is provided by customer the following must be adhered to:

3.1 The material must be protected against bad weather, dust and damages.

3.2 Thief-proof storing.

3.3 Panels must be transported and stored horizontally and always panel surface on panel surface.

3.4 If the storeroom of intermediate storing is far away from the installation room the customer must transport the material to the installation room as soon as the installation starts.

3.5 If the installation cannot be finished due to reasons caused by the customer – thief-proof intermediate storing must be provided by the customer free of charge for MERO-TSK. Eventual theft is on customer's account.

4. Requirements regarding installation room

4.1 The area where MERO-TSK system floor will be installed must be free of any materials and framework. Operations by other trades during installation are strictly interdicted.

4.2 The installation room must be clean (dust-free), dry and protected against bad weather. The gluing of pedestals and the floor sealing require a raw subfloor free of laitance and plaster or mortar residues.

4.3 The raw subfloor for hollow floors which are used as an air plenum must be sealed. This should be done by MERO-TSK due to warranty reasons and is charged separately.

4.4 If the floor sealing is provided by customer it is absolutely necessary that the used floor sealing compounds with the raw subfloor and is compatible with our pedestal glue. Furthermore, the sealing must be applied early enough so that the floor is dry and accessible when the installation of the system floor starts. If the sealing is provided by customer our performance starts at the upper edge of the applied sealing.

4.5 The customer must provide the necessary power for lighting. Electrical connections for 220V and 380V/25A must be available free of charge.

4.6 For floating floor screed water connection of $\frac{3}{4}$ " with a minimum pressure of 3,5 bar must be available.

4.7 The room temperature during the installation must be at least +13°C. The relative air humidity should be 40-65% and the residual moisture of the concrete maximum 4-6%.

For floating floor screeds the temperature range of +5° to +30° must be strictly observed.

5. Modifications and purchase works must be ordered in written by our form "Order of purchase works" and signed after termination of the works.

6. Damages

We refuse being accused for modifications, soiling or inappropriate handling of the system floor after termination of the installation.

Wet hollow floors (screeds) reach full load capacity after 28 days. After 1-3 days walking on the floor is possible. Partial loads can be applied after 3-5 days, however, only after approval of our qualified personnel.

7. Waiting times, additional travelling

Additional travelling and waiting times for our installation personnel which will become necessary due to non-compliance of agreed dates or the missing of the afore-said technical requirements or other circumstances caused by the customer (also force majeure) will be additionally charged by MERO-TSK. Additional travelling will be charged ex Wurzburg.

8. Acceptance

After termination of the works our supervisor will issue a confirmed measurement and performance statement and an acceptance report. These documents must be confirmed by the site manager. Small remaining works do not allow to refuse the acceptance.

* If on individual contract not otherwise agreed. If single items have been agreed on individual contract basis remain all other items unaffected.